



पोलीस आयुक्त अमरावती (शहर) यांचे कार्यालय,

मालटेक डी जवळ, कॅम्प रोड, अमरावती.

दुरध्वी क्र मांक ०७२१-२५५१००१ फॅक्स / .०७२१-२५५१०१०.

ई मेल- cp.amravati@mahapolicе.gov.in.

क्रमांक:पोआअ/लेखा शाखा-पोकनि/पोलीस प. स्कुल-नुतनिकरण -दरपत्रक / 1587 2023 दि 16/2023

7 JUN 2023

दरपत्रक

पोलीस आयुक्त कार्यालय अमरावती शहर यांचे कल्याणकारी योजने अंतर्गत पोलीस कल्याण निधी मधुन कार्यरत असलेल्या पोलीस पब्लिक स्कुल चे खालील प्रमाणे किरकोळ दुरुस्ती व बांधकाम करण्यास स्थानिक स्तरावरील नोंदणीकृत बांधकाम कंत्राटदाराकडुन व्दिलिफाफा पध्दतीने दरपत्रके दिनांक १४/६/२०२३ पर्यंत मागविण्यात येत असुन करावयाचे कामाचे जोडपत्राच्या प्रती सोबत जोडल्या आहेत. या बाबतची सविस्तर माहीती तसेच अटी व शर्ती व इतर सुचणा या संकेतस्थळावर उपलब्ध करुन देण्यात आल्या आहेत.

अ.क्र	कामाचे स्वरुप
१	Repairing Work of police public school Building at Amravati
२	Repairing Work of chainlink fencing work to police public school Building at Amravati
३	Colouring (distemper paint) work to police public school Building at Amravati

सदरचे पत्र हे पोलीस आयुक्त कार्यालयाचे www.amravaticitypolice.gov.in या संकेतस्थळावर अपलोड करण्यात आलेले आहेत. प्राप्त दरपत्रका पैकी दरपत्रक स्विकृत करण्याचा अंतिम अधिकार पोलीस आयुक्त अमरावती शहर यांनी राखुन ठेवला आहे. हयाची कृपया नोंद घ्यावी. तरी इच्छुक दरपत्रक धारकांनी दोन लिफाफा पध्दतीनुसार दरपत्रके या कार्यालयास विहित मुदतीत सादर करावी.

(मा. पोलीस आयुक्त यांचे मान्यतेने)

(सागर पाटील)

पोलीस उपायुक्त (मुख्यालय)

पोलीस आयुक्त कार्यालय अमरावती शहर

प्रती,

पोलीस निरीक्षक, पो. स्टे सायबर,

सदरचे दरपत्रक या कार्यालयाचे संकेतस्थळावर दिनांक १५/०६/२०२३ पर्यंत प्रसिध्द करावे.

प्रत माहीती व कार्यवाहीस,

पोलीस निरीक्षक, कल्याण शाखा. पोलीस आयुक्त कार्यालय अमरावती शहर.



MEASUREMENTS

Name of Work :- Repairing work of Police Public School Building at Amravati

SR. No.	ITEMS OF WORK	No.	L	B	D	QTY	Unit
1	Removing the existing cement plaster of any thickness without causing dust nuisance and stacking the debris upto a distance of 50 metres or spreading in the compound and cleaning the site etc Spec.No. : As directed by Engineer in charge. (SSR Sr No.984, Item No.32.33)	1	x 30.00	x 3.00		90.00	Sq.m.
	Removing old Plaster						
	Back Side Wall						
	Total Qty					90.00	Sq.m.
2	Providing sand faced plaster externally in cement mortar using approved screened sand, in all positions including base coat of 15 mm thick in cement mortar 1:4 using waterproofing compound at 1 kg per cement bag curing the same for not less than 2 days and keeping the surface of the base coat rough to receive the sand faced treatment 6 to 8 mm thick in cement mortar 1:4 finishing the surface by taking out grains and curing for fourteen days scaffolding etc.complete. Spec.No.: Bd.L.7/Page NO.369 (SSR Sr.No.963, Item No.32.11)						
	Back Side Wall						
	Deduction of Window	1	x 30.00	x	x 3.00	90.00	Sq.m.
	Windows	12	x 0.90	x	x 0.60	-6.48	
	Total Qty. =					83.52	Sq.m.
3	Providing structural steel work in trusses, other similar trussed purlins and members with all bracing, gusset plates etc. as per detailed designs and drawings or as directed including cutting, fabricating, hoisting, erecting fixing in position, Making riveted/ bolted/ welded connection and one coat of anticorrosive paint and over it 2 coats of oil painting approved quality and shade etc. Spec.No.: Bd.C.8 Page No. 278 (SSR Sr. No.819, Item No.23.04)						
	For Passage Shed						
	Size 50x50x6mm	2	x 3.00	x	x 4.50	27.00	Kg.
	Vertical Support						
						27.00	Kg.
	Total Qty. =					0.027	MT.
4	Providing and laying matt finish ceramic tiles of having size 30 cm x 30 cm confirming to I.S.15622/2006 (group D II-A) and 7 to 8 mm thick for flooring in required position laid on a bed of 1:4 cement mortar including cement float, filling joint with white/colour cement slurry cleaning curing etc. complete. Spec.No.: Bd.M.12 Page No. 385 (SSR Sr.No.1011, Item No.33.24)						
	For Toilet Block	2	x 1.00	x	x 1.20	2.40	Sq.m.
	Total Qty. =					2.40	Sq.m.

5 Providing and laying ceramic tiles having size 30 cm. x 45 cm. confirming to corresponding I.S. for dado and skirting in required position with readymade adhesive mortar of approved quality on plaster of 1:2 cement mortar including joint filling with white/ colour cement slurry cleaning curing etc. complete.

Spec.No.: Bd.M.13 Page No. 386
(SSR Sr.No.1013, Item No.33.26)

For Toilet Block

Wall tiles	2	x	1.00	x	1.20	Sqm.	2.40
	2	x	1.20	x	1.20		2.88
Deduction for Door D3	1	x	0.75	x	1.20		-0.90

Total Qty. = 4.38 Sqm.

6 Providing and fixing fiber glass reinforced polyester door shutter 30 mm thick as per IS 14856 (2000) (Reaffirmed 2006) without ventilator including chromium plated fixtures and fastening with chromium plated handles on both sides, etc. complete

Spec. No. : As directed by Engineer incharge.

(SSR Sr.No.1254, Item No.39.58)

Door Shutter

For W.C.	4	x	0.75	x	2.10	Sqm.	6.30
----------	---	---	------	---	------	------	------

Total Qty. = 6.30 Sqm.

7 Providing and fixing M.S. grill door 24 kg/sqm of various size as per detailed drawings without hot dip coating, iron fixtures and fastenings and 3 coats of oil painting etc

Spec. No. : As directed by Engineer incharge.

(SSR Sr.No.1224, Item No.39.31)

For Toilet Block

M.S. Grill Door	2	x	1.05	x	2.10	Sqm.	4.41
-----------------	---	---	------	---	------	------	------

Total Qty. = 4.41 Sqm.

8 Providing and fixing 22 B.W.G. plain FRP sheets on top of weather shed, including scaffolding, fixing by means of nut and bolts or as directed etc. complete. (Brackets of 70 x 45 mm to be paid separately)

Spec. No. : As directed by Engineer incharge.

(SSR Sr.No.1284, Item No.39.89)

For School Building

For Windows	12	x	0.90	x	0.60	Sqm.	6.48
-------------	----	---	------	---	------	------	------

Total Qty. = 6.48 Sqm.

9 Providing and fixing sheet glass of 24 oz. for all size including putty etc. complete

Spec. No. : BD-S Page No. 465 to 467

(SSR Sr.No.1221, Item No.39.28)

For School Building

For Windows Glass	1	x	0.45	x	1.20	Sqm.	0.54
	1	x	0.75	x	1.20		0.90

Total Qty. = 1.44 Sqm.

10	Providing and fixing Orissa type white glazed earthenware 575 mm water closet pan including S trap with earthenware foot rests, cast iron soil and vent pipe upto outside face of the wall 1:2:4 brick bat lime concrete bedding without flushing tank and its accessories etc. complete.	Spec. No. : As directed by Engineer incharge. (SSR Sr.No.1401, Item No.42.30)	2	2.00	No.	Total Qty. = 2.00	No.
		W.C. Pan					
11	Providing and fixing H.D.P container Syntex or alike one piece moulded water tank made out of low density polythylar and built corrugation including of delivery up to destination hoisting and fixing of accessories such as inlet, outlet overflow of all tanks capacity above 1000 to 20,000 litres	Spec. No. : As directed by Engineer incharge. (SSR Sr.No.1425, Item No.42.54)	1 x	500.00	Ltr.	Total Qty. = 500.00	Ltr.
		Water Tank					
12	Providing and laying in trenches 20 mm dai. CPVC pipe including necessary excavation, fittings. Refilling trenches etc. complete. Including removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete.	Spec. No. : As directed by Engineer incharge. (SSR Sr.No.1433, Item No.42.62)	2 x	6.00	Rmt.	Total Qty. = 12.00	Rmt.
13	Providing and fixing 100 mm dia stabiliser pipe/ P.V.C. soil vent/waste pipe and with necessary fixtures and fitting such as bends, tees, single junctions, slotted vent, clamps etc. complete.	Spec. No. : As directed by Engineer incharge. (SSR Sr.No.1423, Item No.42.52)	1 x	6.00	Rmt.	Total Qty. = 6.00	Rmt.
14	Providing and fixing 20 mm dia. screw down bib/ stop tap of brass including necessary socket union nut complete.	Spec. No. : Bd.V.8 Page No. 554 (SSR Sr.No.1335, Item No.41.41)	4	4.00	No.	Total Qty. = 4.00	No.

MEASUREMENTS

Name of Work :- Repairing work of Chainlink Fencing Work to Police Public School Building at Amravati

SR. No.	ITEMS OF WORK	No.	L	B	D	QTY	Unit
1	Providing and erecting 1.5 metre high wire fencing with seven rows of barbed wire supported on M.S.Angles (50mm x 50mm x 6mm) at 2.5 Metres, Center to center including excavating pits for foundqtion, fixing post in cement cocnrete 1:4:8 of size 45 x 45 x 45 cm fastening the wire and painting the M.S.Angles with one coat of red lead primer and two coats of painting etc.complete.						
	Spec.No. : Bd.W.3 Page No.583 (SSR Sr No.1524, Item No.44.09)						
		1	x	150.00		150.00	Rmt.
						Total Qty	150.00 Rmt.



MEASUREMENTS

Name of Work :- Colouring work of Police Public School Building at Amravati

SR. No.	ITEMS OF WORK	No.	L	B	D	QTY	Unit
1	Providing and applying Two coats of wall care Putty on plastered surface and Ceiling and Walls to prepare surface even and smooth of approved make, etc complete.						
	Spec.No.: As directed by Engineer in charge. (SSR Sr.No.985, Item No.32.34)						
	For School Building						
	For Class Room 4 No's						
	Long Wall	8	x 7.50	x	x 3.00	180.00	Sqm.
	Short Wall	8	x 3.30	x	x 3.30	87.12	
	Deduction of Door	12	x 1.00	x	x 2.10	-25.20	
	Deduction of Windows	12	x 0.90	x	x 0.60	-6.48	
						Total Qty. = 235.44	Sqm.
2	Providing and applying priming coat on concrete/ masonry/ Asbestos Cement plastered surfaces including scaffolding if necessary, preparing the surface by thoroughly cleaning oil, grease, dirt and other foreign matter and sand papering as required etc. complete.						
	Spec.No.: As directed by Engineer in charge. (SSR Sr.No.1090, Item No.35.21)						
	Same Qty. as Item No. 1					235.44	Sqm.
						Total Qty. = 235.44	Sqm.
3	Providing and applying washable oil-bound distemper of approved colour and shade to old and new surfaces in two coats including scaffolding, preparing the surfaces. (excluding the primer coat.) etc. complete.						
	Spec.No.: As directed by Engineer in charge. (SSR Sr.No.1106, Item No.36.11)						
	Same Qty. as Item No. 1					235.44	Sqm.
						Total Qty. = 235.44	Sqm.



पोलीस आयुक्त अमरावती (शहर) यांचे कार्यालय,

मालटेक डी जवळ, कॅम्प रोड, अमरावती.

दुरध्वी क्र मांक ०७२१-२५५१००१ फॅक्स / .०७२१-२५५१०१०.

ई मेल- cp.amravati@mahapolice.gov.in.

साक्षात्

क्रमांक:पोआअ/लेखा शाखा-पोकनि/पोलीस प. स्कुल-नुतनिकरण -दरपत्रक / 15/2023 दि 16/2023
7 JUN 2023

दरपत्रक

पोलीस आयुक्त कार्यालय अमरावती शहर यांचे कल्याणकारी योजने अंतर्गत पोलीस कल्याण निधी मधुन कार्यरत असलेल्या पोलीस पब्लीक स्कुल चे खालील प्रमाणे किरकोळ दुरुस्ती व बांधकाम करण्यास स्थानिक स्तरावरील नोंदणीकृत बांधकाम कंत्राटदाराकडुन व्दिलिफाफा पध्दतीने दरपत्रके दिनांक १४/६/२०२३ पर्यंत मागविण्यात येत असुन करावयाचे कामाचे जोडपत्राच्या प्रती सोबत जोडल्या आहेत. या बाबतची सविस्तर माहिती तसेच अटी व शर्ती व इतर सुचना या संकेतस्थळावर उपलब्ध करुन देण्यात आल्या आहेत.

अ.क्र	कामाचे स्वरुप
१	Repairing Work of police public school Building at Amravati
२	Repairing Work of chainlink fencing work to police public school Building at Amravati
३	Colouring (distemper paint) work to police public school Building at Amravati

सदरचे पत्र हे पोलीस आयुक्त कार्यालयाचे www.amravtcitypolice.gov.in या संकेतस्थळावर अपलोड करण्यात आलेले आहेत. प्राप्त दरपत्रका पैकी दरपत्रक स्विकृत करण्याचा अंतिम अधिकार पोलीस आयुक्त अमरावती शहर यांनी राखुन ठेवला आहे. हयाची कृपया नोंद घ्यावी. तरी इच्छुक दरपत्रक धारकांनी दोन लिफाफा पध्दतीनुसार दरपत्रके या कार्यालयास विहित मुदतीत सादर करावी.

(मा. पोलीस आयुक्त यांचे मान्यतेने)

(सागर पाटील)

पोलीस उपायुक्त (मुख्यालय)

पोलीस आयुक्त कार्यालय अमरावती शहर

प्रती,

पोलीस निरीक्षक, पो. स्टे सायबर,

सदरचे दरपत्रक या कार्यालयाचे संकेतस्थळावर दिनांक १५/०६/२०२३ पर्यंत प्रसिध्द करावे.

प्रत माहिती व कार्यवाहीस,

पोलीस निरीक्षक, कल्याण शाखा. पोलीस आयुक्त कार्यालय अमरावती शहर.



MEASUREMENTS

Name of Work :- Repairing work of Police Public School Building at Amravati

SR. No.	ITEMS OF WORK	No.	L	B	D	QTY	Unit
1	Removing the existing cement plaster of any thickness without causing dust nuisance and stacking the debris upto a distance of 50 metres or spreading in the compound and cleaning the site etc Spec.No. : As directed by Engineer in charge. (SSR Sr No.984, Item No.32.33)						
	Removing old Plaster						
	Back Side Wall	1	x 30.00	x 3.00		90.00	Sqm.
	Total Qty					90.00	Sqm.
2	Providing sand faced plaster externally in cement mortar using approved screened sand, in all positions including base coat of 15 mm thick in cement mortar 1:4 using waterproofing compound at 1 kg per cement bag curing the same for not less than 2 days and keeping the surface of the base coat rough to receive the sand faced treatment 6 to 8 mm thick in cement mortar 1:4 finishing the surface by taking out grains and curing for fourteen days scaffolding etc.complete. Spec.No.: Bd.L.7/Page NO.369 (SSR Sr.No.963, Item No.32.11)						
	Back Side Wall	1	x 30.00		x 3.00	90.00	Sqm.
	Deduction of Window						
	Windows	12	x 0.90	x	x 0.60	-6.48	
	Total Qty. =					83.52	Sqm.
3	Providing structural steel work in trusses, other similar trussed purlins and members with all bracing, gusset plates etc. as per detailed designs and drawings or as directed including cutting, fabricating, hoisting, erecting fixing in position, Making riveted/ bolted/ welded connection and one coat of anticorrosive paint and over it 2 coats of oil painting approved quality and shade etc. complete. Spec.No.: Bd.C.8 Page No. 278 (SSR Sr. No.819, Item No.23.04)						
	For Passge Shed						
	Size 50x50x6mm	No's	Length	x	Wt./Rmt		
	Vertical Support	2	x 3.00	x	4.50	27.00	Kg.
						27.00	Kg.
	Total Qty. =					0.027	MT.
4	Providing and laying matt finish ceramic tiles of having size 30 cm x 30 cm confirming to I.S.15622/2006 (group D II-A) and 7 to 8 mm thick for flooring in required position laid on a bed of 1:4 cement mortar including cement float, filling joint with white/colour cement slurry cleaning curing etc. complete. Spec.No.: Bd.M.12 Page No. 385 (SSR Sr.No.1011, Item No.33.24)						
	For Toilet Block	2	x 1.00	x	1.20	2.40	Sqm.
	Total Qty. =					2.40	Sqm.

5	Providing and laying ceramic tiles having size 30 cm. x 45 cm. conforming to corresponding I.S. for dado and skirting in required position with readymade adhesive mortar of approved quality on plaster of 1:2 cement mortar including joint filling with white/ colour cement slurry cleaning curing etc. complete.
	Spec.No.: Bd.M.13 Page No. 386 (SSR Sr.No.1013, Item No.33.26)
	For Toilet Block
	Wall tiles 2 x 1.00 x 1.20 2.40 Sqm.
	2 x 1.20 x 1.20 2.88
	Deduction for Door D3 1 x 0.75 x 1.20 -0.90
	Total Qty. = 4.38 Sqm.
6	Providing and fixing fiber glass reinforced polyester door shutter 30 mm thick as per IS 14856 (2000) (Reaffirmed 2006) without ventilator including chromium plated fixtures and fastening with chromium plated handles on both sides, etc. complete
	Spec. No. : As directed by Engineer incharge. (SSR Sr.No.1254, Item No.39.58)
	Door Shutter
	For W.C. 4 x 0.75 x 2.10 6.30 Sqm.
	Total Qty. = 6.30 Sqm.
7	Providing and fixing M.S. grill door 24 kg/sqm of various size as per detailed drawings without hot dip coating, iron fixtures and fastenings and 3 coats of oil painting etc
	Spec. No. : As directed by Engineer incharge. (SSR Sr.No.1224, Item No.39.31)
	For Toilet Block
	M.S. Grill Door 2 x 1.05 x 2.10 4.41 Sqm.
	Total Qty. = 4.41 Sqm.
8	Providing and fixing 22 B.W.G. plain FRP sheets on top of weather shed, including scaffolding, fixing by means of nut and bolts or as directed etc. complete. (Brackets of 70 x 45 mm to be paid separately)
	Spec. No. : As directed by Engineer incharge. (SSR Sr.No.1284, Item No.39.89)
	For School Building
	For Windows 12 x 0.90 x 0.60 6.48 Sqm.
	Total Qty. = 6.48 Sqm.
9	Providing and fixing sheet glass of 24 oz. for all size including putty etc. complete
	Spec. No. : BD-S Page No. 465 to 467 (SSR Sr.No.1221, Item No.39.28)
	For School Building
	For Windows Glass 1 x 0.45 x 1.20 0.54 Sqm.
	1 x 0.75 x 1.20 0.90
	Total Qty. = 1.44 Sqm.



10	Providing and fixing Orissa type white glazed earthenware 575 mm water closet pan including S trap with earthenware foot rests, cast iron soil and vent pipe upto outside face of the wall 1:2:4 brick bat lime concrete bedding without flushing tank and its accessories etc. complete.				
	Spec. No. : As directed by Engineer incharge. (SSR Sr.No.1401, Item No.42.30)				
	W.C. Pan	2		2.00	No.
				Total Qty. =	2.00 No.
11	Providing and fixing H.D.P container Syntex or alike one piece moulded water tank made out of low density polythylar and built corrugation including of delivery up to destination hoisting and fixing of accessories such as inlet, outlet overflow of all tanks capacity above 1000 to 20,000 litres				
	Spec. No. : As directed by Engineer incharge. (SSR Sr.No.1425, Item No.42.54)				
	Water Tank	1	x 500.00	500.00	Ltr.
				Total Qty. =	500.00 Ltr.
12	Providing and laying in trenches 20 mm dai. CPVC pipe including necessary excavation, fittings. Refilling trenches etc. complete. Including removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete.				
	Spec. No. : As directed by Engineer incharge. (SSR Sr.No.1433, Item No.42.62)				
		2	x 6.00	12.00	Rmt.
				Total Qty. =	12.00 Rmt.
13	Providing and fixing 100 mm dia stabiliser pipe/ P.V.C. soil vent/waste pipe and with necessary fixtures and fitting such as bends, tees, single junctions, slotted vent, clamps etc. complete.				
	Spec. No. : As directed by Engineer incharge. (SSR Sr.No.1423, Item No.42.52)				
		1	x 6.00	6.00	Rmt.
				Total Qty. =	6.00 Rmt.
14	Providing and fixing 20 mm dia. screw down bib/ stop tap of brass including necessary socket union nut complete.				
	Spec. No. : Bd.V.8 Page No. 554 (SSR Sr.No.1335, Item No.41.41)				
		4		4.00	No.
				Total Qty. =	4.00 No.

MEASUREMENTS

Name of Work :- Repairing work of Chainlink Fencing Work to Police Public School Building at Amravati

SR. No.	ITEMS OF WORK	No.	L	B	D	QTY	Unit
1	Providing and erecting 1.5 metre high wire fencing with seven rows of barbed wire supported on M.S.Angles (50mm x 50mm x 6mm) at 2.5 Metres, Center to center including excavating pits for foundqtion, fixing post in cement cocnrete 1:4:8 of size 45 x 45 x 45 cm fastening the wire and painting the M.S.Angles with one coat of red lead primer and two coats of painting etc.complete.						
	Spec.No. : Bd.W.3 Page No.583 (SSR Sr No.1524, Item No.44.09)						
		1	x	150.00		150.00	Rmt.
						Total Qty	150.00 Rmt.

MEASUREMENTS

Name of Work :- Colouring work of Police Public School Building at Amravati

SR. No.	ITEMS OF WORK	No.	L	B	D	QTY	Unit
1	Providing and applying Two coats of wall care Putty on plastered surface and Ceiling and Walls to prepare surface even and smooth of approved make, etc complete.						
	Spec.No.: As directed by Engineer in charge.						
	(SSR Sr.No.985, Item No.32.34)						
	For School Building						
	For Class Room 4 No's						
	Long Wall	8	x	7.50	x	x 3.00	180.00 Sqm.
	Short Wall	8	x	3.30	x	x 3.30	87.12
	Deduction of Door	12	x	1.00	x	x 2.10	-25.20
	Deduction of Windows	12	x	0.90	x	x 0.60	-6.48
						Total Qty. =	235.44 Sqm.
2	Providing and applying priming coat on concrete/ masonry/ Asbestos Cement plastered surfaces including scaffolding if necessary, preparing the surface by thoroughly cleaning oil, grease, dirt and other foreign matter and sand papering as required etc. complete.						
	Spec.No.: As directed by Engineer in charge.						
	(SSR Sr.No.1090, Item No.35.21)						
	Same Qty. as Item No. 1					235.44	Sqm.
						Total Qty. =	235.44 Sqm.
3	Providing and applying washable oil-bound distemper of approved colour and shade to old and new surfaces in two coats including scaffolding, preparing the surfaces. (excluding the primer coat.) etc. complete.						
	Spec.No.: As directed by Engineer in charge.						
	(SSR Sr.No.1106, Item No.36.11)						
	Same Qty. as Item No. 1					235.44	Sqm.
						Total Qty. =	235.44 Sqm.